



FY17 Vermont Better Roads Grant Application

Please com	plete this page ONCE a	nd return with y	your Grant Category Ap	plication(s)
Town/Org	anization: <u>Somerset</u> C	Contact Person	(s): Robert Faley	
Address:	359 Bowen	Rd.	Bennington, VT	05201
	Street Address		Town	Zip
	Email: Robert.Faley@ve	ermont.gov	Phone: (802) 447-	<u>2790</u>
	e e e	9		
	DUNS #: <u>96789567</u>	8	Fiscal Year End Month (MM): 06
	Accounting System:	X Automated	☐ Manual	☐ Combination
	the suggested document our application have bee		below to ensure that all	of the relevant items
G Ite V Pi Sl di Ph Lei	roject Location Map (plea ketch of proposed erosion istances in feet Also show approxim property lines oto(s) of the project area tters of Support (RPC, VT	ne per category, r labor, equipme please break de ase show location on control measu mate location of a rans District Tec onflict or Catego	/project) ent, and materials (see ent, and materials (see ent) on of affected water) ures or other management town/other right-of-water chnical Staff, ANR Rivers	i.e. different grant sources) ent practices, including







Vermont Better Roads Grant Program Application

Please complete one application per category and/or project you are applying for. You may make copies of the application for multiple applications per category and/or multiple categories.

Please check the Category you are applying for:

- B. Correction of a Road Related Erosion Problem and/or Storm water Mitigation Retrofit for both gravel and paved roads
- C. Correction of a Stream Bank or Slope Related Problem
- D. Structure/culvert upgrades

Town/Organization:	S	omerset			
Project Name: Re	eplace deteriorate	ed culvert.			
Road Name:	Somerset Rd	TI	ተ #: 1 :	Structure # (if applicable	e):
Road Type: Paved	or <mark>Unpaved</mark> (d	circle one)		Curbed or Uncurbed	(circle one)
	Class 1 (Class 2 Class 3	Class 4	(circle one)	
Watershed: Deerfield	River.				
Please provide a thoro	ugh description o	f the problem (e	x. Roadwa	y has steep slope with I	no ditch which is
causing roadway erosi	on):				
Culvert failure is causi	ng ditch line wate	er to build up and	d cross ro	adway, causing erosion o	of road surface and
allowing movement of s		avel into river. Pi	pe steel a	nd is under sized with la	rge chunks of
asphalt coating being di	scharged.	80			

Description of Project and how you plan to complete the work (ex. Stone line 500' of ditch by reshaping ditch and stone lining, working from the top of the project down to the bottom):

<u>Ditch area for dewatering into lower culvert.</u> Removal of old 18' ACCMP and install new 24" HDPE corrugated pipe with end section. Stone line ditch inlet to armor walls. Back fill with native soils compacted. Resurface road with gravel where needed.

Expected Effects (+ & -) on water quality (ex. Erosion will be eliminated by placing the stone ditch):

Road surface will need less maintenance after controlling water over flowing roadway. Replacement will allow water to freely flow through culvert and minimize the amounts of sediment entering the river improving water quality and increase the likelihood of microorganisms and aquatic life to pass.





The second secon	m, lake, or storm water system that outlets directly to 0-250' 250'+
, re	
Progress to Date:	a e
None	
Is there an emergency reason this project must be co	ompleted quickly? If yes, please explain:
	ater back up and is removing more road surface each time
t floods over. May cause roadway to become unstab	ie and wash out into river.
Has this project been identified through a municipal i culvert inventory, or other management plan? If yes	road inventory, capital budget plan, tactical basin plan, , please list which.
Yes: Is noted that needs to be corrected on Road Inve	ntory. No
Please list any professionals you may have contacted	d for assistance with this project (ANR River
Management Engineer, Army Corps of Engineers, V	Trans District Technical staff, Basin Planner etc.):
VTrans District Technical staff	,
2	
Is the project located in the town "Right of Way?" Y	es, No, Both (if "Both" please explain further).
Yes, this is a class 3 roadway and is a 3 rod roa	d (24.75'.) All work will be in the towns' right of way.
Will the town road crew complete this work? Yes, N	o, Some (if "some" please explain further).
Work to be done using VTrans work force. Somerset is	an Unorganized Town.
-	
	*
	e e






Describe how the grant funds will be spent and/or attach a project budget: Cost estimate attached
How do you plan to meet the required 20% match on this grant?:
Town budget for maintenance.
Requested Grant Amount (\$20,000 max Category B, \$40,000 max Categories C & D): \$13,800.80
Estimated Total Project Cost (including 20% local match): \$17,251.00
Estimated Completion Date: 10/15/2016
REQUIRED ATTACHMENTS:
Itemized Cost Estimate (labor, equipment, materials) (For assistance, call Better Backroads at 802-828-4585) Project Location Map
(Please show location of affected water; 1:12,000 USGS map, If possible) Sketch of proposed erosion control measures, including: Distances (ft.)
Estimate of waste & borrow quantities Approx. location of town/other right-of-way and/or property lines
Photo(s) of the project area. Agreement for Entry and/or Deed of Easement (if project is outside Town ROW).
If project involves stream or river/road conflict, include documentation of consultation with a River Management Engineer.
Other appropriate supporting documents.
By signing this application I certify that all the information provided is accurate to the best of my knowledge. We will comply with all the requirements of the grant including making our books available for audit if required.
SIGNATURE OF APPLICANT: (Must be Town Administrator/Manager or Select Board Chair)
Name: KLAT-Region Title DTA - SW REGION





Somerset TH-1 Ditching Estimate 4/12/2016



*Roadway washed from failed culvert, water traveled down the road has caused subbase exposure. Note gravel in ditches that has washed.





Construction quantity and cost estimates

Materials/Equipment	Quantity	Unit	Unit Price	Total Cost
Trucking	40 Hours	2	\$185/hour	\$7,400.00
Excavator	16 Hours	1	\$120/hour	\$1,920.00
Roller	4 Hours	1		
Ditching	LF	700	. * .,	•
Loader	10 Hours	1	\$115./hour	\$1,150.00
Stone Type I	25 CY	-	\$25/CY	\$625.00
Culvert pipe	LF	60	\$16.00 LF	\$960.00
End sections	PU	1	\$310.00	\$310.00
Surface Gravel	64 CY	-	\$12./CY	\$786.00
Seed & Mulch	-	-		\$300.00
labor	10 Hours	2	\$65/hour	\$1,300.00
Traffic control	-	-		\$2,500.00
Total				\$17,251.00

Construction Notes: Construction specification and guidelines for ditching maintenance - See Vermont Better Back Roads Manual 2009, and the 2015 VTrans hydraulic Manual





